665

CHITALDRUG DIVISION.

Notice dated 7th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 17th January 1928, for restoring Kandagal Tank, Reg. No. 38 of Davangere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 100 in cash, as earnest money, and be superscribed "Tender for restoring Kandagal Tank, Reg. No. 38 of Davangere Taluk".

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for restoring Kandagal Tank, Register No. 38 of Davangere Taluk.

No.	Items of work	Per	Quantity
	BUND R. L. 55·00.		
1	Earth work to bund including consolidation	C.yd.	2,788
2	Turfing	Sqr.	291·06
3	New stone revetment	C.yd.	402
4	Repairing old revetment	...	L.S.
5	New B. M. Stones	each	2
6	Register No. stone including painting, etc.	"	1
7	Grade stones	"	8
8	Removing and refixing old grade stones with painting, etc. ...	"	20
9	Gauge stone	"	1
	SLUICE.		
1	Petty repairs to sluice providing and fixing plug rod locking arrangements, etc.	...	L.S.
	WASTE WEIR R. L. 50·00.		
1	Earth work excavation to body wall and returns using the earth to raise the ground in continuation of the weir to R. L. 50·00.	C.yd.	32
2	Rough stone work to body wall and returns	"	57
3	Rough stone apron including jelly filling	"	98
4	Stone jelly below the front portion of apron wherever there is scour.	C.yd.	10

Dated 7th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 17th January 1928, for constructing a Town Hall at Holalkere, in Holalkere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

	Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 in cash as earnest money, and be superscribed "Tender for constructing a Town Hall at Holalkere in Holalkere Taluk."

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing a Town Hall Building at Holalkere, Chitaldrug District.

No.	Items of work	Per	Quantity
1	Earthwork excavation	C.yd.	27
2	Concrete in lime mortar	C.ft.	1,334
3	Stone in mud	"	1,539
4	Burnt brick in clay	"	2,511
5	Burnt brick in chunam arch work	"	189
6	Do sides doors, etc.	"	434
7	Burnt stone slabs 6" thick roughly dressed... ...	S.ft.	164
8	Teak wood doors pannelled shutters 1¼" frame 3½" × 5" thick, hinges, hooks, iron fittings, etc. ..	"	81
9	Teak wood windows, single shutters, in 4 halves, half glazed and half pannelled with ¾" iron bars and fittings, frame 3" × 4" hinges, hooks, etc., complete	"	236
10	Teak wood ventilators glazed shutters	"	53
11	Teak wood semicircular gothic shape fan lights over doors and windows with glazed shutters, hinges, etc.	"	31
12	Parapet wall in verandha brick in mortar 4' high ...	R.ft.	6
13	Foliated arch work in front verandah ...	No.	1
14	Teak wood wall-shelves	S.ft.	35
15	Forming base and caps of pillars in front of verandah ...	No.	4
16	Do do by the sides of windows in front	"	6
17	Teak wood wrought and put up with oiling	C.ft.	132·43
18	Roll steel girders hoisting painting Ry. freight, complete	Cwt.	14
19	Pukka terracing	Sqr.	12·72

No.	Items of work	Per	Quantity
20	12" Cornice with terrace brick plaster to the shape of lovey with brackets as per design	R.ft.	97
21	Cornice 7½" thick	"	138
22	Parapet wall top of roof 1½' high 3/8' thick with ¾' perforated blocking course	"	228
23	Plastering with lime mortar with white and colour washing	Sqr.	62·94
24	Cement pointing to basement	"	3·54
25	Flooring with 1st Class Mangalore Tiles on 3" concrete bed and cement pointing	Sqr.	3·19
26	Flooring with Cudapah Slabs, 1½" to 2" thick on 3" concrete bed and pointing with cement ...	Sqr.	1·26
27	Ornamental niches over windows	L.s.	2
28	Painting with Chacolate paint	Sqr.	5·08

A. TANDONI RAO,
Executive Engineer.

GAUGING AND UPPER CHANNELS DIVISION, MYSORE.

Abstract Notification dated 26th November 1927.

"Attention of the public is invited to the notification dated 26th November 1927 published on pages 1038 and 1039 of Part VI of the *Mysore Gazette* dated 1st December 1927, calling for tender for constructing Utsvagudi for Sriramadevaru and Sri Narayanaswami temples at Yedatore New Town."

K. NARAYANA IYENGAR,
Executive Engineer,
Gauging and Upper Channels Division,
Mysore.

MYSORE GOVERNMENT ELECTRICAL DEPARTMENT.

SALE OF SOLID HARD DRAWN BARE COPPER WIRE.

Dated 7th December 1927.

Sealed tenders for the purchase of 20 tons of Solid Hard Drawn Bare Copper Wire, as per specification given below, will be received in the office of the undersigned up to 12 noon of the 14th January 1928.

Cross section of wire	... 0·829 sq. in. (1,06,000 cir. mils).
Diameter of wire	... 0·325" (325 mils).
Weight in lbs. per mile	... 1,680 lbs.

1. The wire is available in reels of about half a mile.

2. The tenders should be superscribed "Tenders for the purchase of copper wire, due on the 14th January 1928, 12 noon" and should be accompanied with an earnest money of Rs. 500.

The earnest money should be sent separately by registered post and should be either in currency notes or cheques drawn on the Mysore Bank or The Imperial Bank of India.

3. The undersigned reserves to himself the right to refuse the highest or any tender without giving any reason therefor.

4. The deposit of the successful tenderer will be retained, and he will be required to execute an agreement and furnish a further deposit of one-fourth of the amount of the tender.

5. Payment in full will have to be made for the quantities of wire removed from our stores and the amount of deposit will be adjusted towards the close of the whole transaction.

6. Delivery will be in the Central Stores, near City Railway Station, and the purchaser will have to make his own arrangements for the transport of the wire from the Stores.

7. Failure to comply with the above conditions will entail the forfeiture of the amounts deposited and the wire will be resold at the risk of the successful tenderer, who will have no claim to profits, if any should accrue in the resale.

8. Arrangements will be made to refund the earnest money of the unsuccessful tenderers immediately the successful tenderer is known.

B. D. NATH.
For *Chief Electrical Engineer.*